

CITY OF CRANBROOK

REQUEST FOR PROPOSAL ARENA DASHER BOARDS CRA2019-R-001

ADDENDUM #1

Date: March 19, 2019

This Addendum is issued to clarify questions that have arisen relating to the expectations in the Request for Proposal.

- 1) The City will provide an area to store the existing dasher boards, glass, and posts. Glass racks will be provided. The contractor will be required to provide necessary pallets to transport the dasher boards. The contractor will be required to transport this material to the storage location.
- 2) The Proposal should include the cost of all the labour to remove the existing dasher boards system, move the old system to storage and to install the new system. Depending on scheduling, the City may be able to provide labour, and would then negotiate with the successful proponent.
- 3) For the purpose of the bid, the number of gates will remain the same as the existing system. However, the City will have some need for additional openings, not fully determined at this time. It would be negotiated into the final contract. Please bid the existing gate openings to be 48 inches wide.
- 4) The existing netting system is on an electric retractable track. It can be lowered directly on to the ice level. The netting should be quoted as black nylon, however the City may look at Kevlar options if it is determined that the netting will be replaced. The net height is 20 feet.
- 5) For the installation, the City will attempt to have some members of City Staff assist as part of their training, however the training should be quoted as per the Request for Proposal.
- 6) The box sizes and configurations will remain as shown on the existing diagrams.
- 7) Proposals should include plans to refurbish the back walls of the players, camera, penalty and scorekeepers boxes. The existing steel framework shall remain in place. The City would like reuse their existing concert rail system that consists of aluminum support posts and 3 feet high tempered glass panels behind these areas. Proposals should include the costs of:
 - a. Replacing HDPE facing, top sill and backer;
 - b. New post sleeves running from the mid rail to the top of dasher frame;
 - c. New acrylic hockey shielding and one piece aluminum support post. The new acrylic support posts need to be of the same shape to utilize the same opening in the top sill and new post sleeves; and
 - d. New rubber flooring, benches, dividers, gates, scorekeepers table.

- 8) The Successful Proponent can arrange to view the back of the board system after the Request for Proposal is awarded, however the actual removal of boards for any slab survey/examination cannot take place until May 6, 2019. The final day of ice use is April 28, 2019.
- 9) The requested gap closure is only required along the length of the arena. The end corners have a metal system that can be re-used. The current gap cover along the length of the dasher boards is a 4 inch strip.
- 10) Proposals should include the cost to rent forklifts and provide a forklift operator. If the City is able to supply a forklift and operator, it will be negotiated in the final contract.

Closing Date

The closing date has been extended to Friday, March 29th, 2019, by 2:30 pm local time.

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED.

Melissa Smith, CPA, CA
Financial Services Manager
City of Cranbrook